BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Office of the Executive Engineer
Electrical Division, Yelahanka Zone
Bruhath Bengaluru Mahanagara Palike

"Schedule B"

Name of Work :- Operation and Maintainence of Musical dancing fountain in Ward No 04 Yelahanka Zone

Sl. No	Qty	Description Of Work	Unit	Quoted Rates	
				In figures	In words
1	150	Skilled Electrician Notification No. KAE 69 tWA 2022, dateds0-l,-2022 Minimum Wages and VDA From 01-04-2024 to 31-03-2024	Days	744.55	Seven Hundred Forty Four Rupees and Fifty Five Paise
2	150	Assistant Technician Semi Skilled KAE 69 tWA 2022, dateds0-l,-2022 Minimum Wages and VDA From 01-04-2024 to 31-03-2024	Days	715.27	Seven Hundred Fifteen Rupees and Twenty Seven Paise
3	3	Annual Maintenance of Music systems. Including repairs to amplifiers, speakers, cables, connectors, required Audio jacks, DVD player etc. b) Music system with amplifier power handling of 500 to 1000 watts RMS	Per Annum	49200	Forty Nine Thousand Two Hundred Rupees
4	85	Supply and Installation of Nozzel made of brass nickel platted with Ball Joint.	Nos	900	Nine Hundred Rupees
5	10	Supply and installation of straight Jet Assembly	Nos	450	Four Hundred Fifty Rupees
6	20	Supply and installation of Arch jet Assembly	Nos	425	Four Hundred Twenty Five Rupees
7	10	Supply and installation of Wpl050 Light Complete Assembly made of diecast aluminium body, black powder coated with reflector.	Nos	8150	Eight Thousand One Hundred Fifty Rupees
8	10	Supply and Installation of 220 volts, AC supply 65 mm Coil For Solenoid valve.	Nos	5150	Five Thousand One Hundred Fifty Rupees
9	212	Operation and Maintenance of LED street lighting system including replacement of damaged/failed /fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **24 to 45 watt LED street lighting System.**	Each	622.5	Six Hundred Twenty Two Rupees and Fifty Paise
10	10	Operation and Maintenance of LED street lighting system including replacement of damaged/failed/fused out components like LED drivers,LED array, MCPCB, surge protective device,wires and switching ON/OFF of street lights at specified timing, furnishing maintenance reports every day, Maintaining movement log of ladder jeep by installing dedicated GPS system with required hardware and software etc, complete, so as to ensure efficient burning of street lights as detailed in tender documents for **200 to 300 watt LED street lightingsystems.**	Each	1700	One Thousand Seven Hundred Rupees
11	95.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to13:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100 Volts as per IS-694:1990.3C x 6 mm2	m	245	Two Hundred Forty Five Rupees
12	0.60	1.1 kV, XLPE or Heat resistant PVC insulated, PVC exutruted Inner Seath Armoured LTUG Cable as per IS-1554 (Part 1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 16 Sqmm, 2 Core, (9 GI Strips - 4 x 0.8 mm)	Km	88418	Eighty Eight Thousand Four Hundred Eighteen Rupees

Executive Engineer
Electrical Division
Yelahanka Zone BBMP
Byatarayanapura, Bangalore-92

13	0.60	Laying of cable in Existing Trench/GI pipe/Stone Ware/RCC Hume pipe using Wooden/Aluminum Rollers as directed by the departmental staff LT Cable 2.5 to 25 Sqmm	Km	20886	Twenty Thousand Eight Hundred Eighty Six Rupees
14	65	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required , utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. All kinds of soils. Depth upto 1.50 m	m^3	262	Two Hundred Sixty Two Rupees
15	130.00	Wiring for lighting /power circui tusing one of FRLS PVC insulated 1100 V grade, multistrand copper wire with low conductor resistance singlecore in open or concealed system of wiring with specified IS694:2010 1.5 mm2	m	26	Twenty Six Rupees

I am prepared to take up the above work at rates quoted in the Schedule 'B'

Contractor

EXECUTIVE ENGINEER (ELEC)
BBMP, Yelahanka Zone